

Project Title: **Proposed Renovation of Office of HRRO at the 4th Floor
of CSC Main Building**

Location: Civil Service Commission - Central Office

Floor Area: 382.00 sq.m

Scope of Work

- 1.0 Dismantling of Existing Tiles and Supply, Delivery and Installation of 60x60cm Homogenous Tiles
- 2.0 Masonry works for window sill
- 3.0 Demolition of Existing Drywall Partition
- 4.0 Installation of Drywall Partition
- 5.0 Demolition of Existing Ceiling
- 6.0 Installation of Ceiling
- 7.0 Rewiring of Electrical and installation of Lighting Fixtures
- 8.0 Supply, Delivery and Installation of Modular workstation
- 9.0 Demolition of existing wall at Comfort room
- 10.0 Dismantling of Existing Tiles at the Comfort Room
- 11.0 Installation of Floor and wall Tiles at the Comfort Room
- 12.0 Repiping of water and sewer line at the Comfort Room
- 13.0 Installation of Plumbing Fixtures at the Comfort Room
- 14.0 Construction of Kitchen Counter

Bill of Materials and Quantities

	<i>Description</i>	<i>Quantity</i>	<i>Unit</i>
2.0	Masonry works for window sill		
	CHB	100.00	pcs
	Sand (bistay)	20.00	bags
	60x60cm Homogenous Tiles	20.00	pcs
	Tile Adhesive	10.00	bags
	Portland Cement	8.00	bags
	Tile Grout	3.00	bags
4.0	Installation of Drywall Partition		
	50x75mmx3m Metal Studs	113.00	pcs
	50x75mmx3m Metal Track	51.00	pcs
	1/4 thk Hardiflex	91.00	pcs
	1/8x 1" Blind Rivets	5.00	boxes
	1/8x 1/2" Blind Rivets	20.00	boxes
	1/8" Stainless Drill Bit (for metal)	4.00	pcs
	1/8" Stainless Drill Bit (for concrete)	4.00	pcs
	Riveter	1.00	pc
	Flat Latex	4.00	tin
	Semigloss Latex	4.00	tin
	Skim Coat	5.00	bags
	2" Gauze Bandage (gasa)	40.00	boxes
	Floor Sanding #100 3M	6.00	m
	Tinting color (raw sienna)	2.00	liter
	Tinting color (yellow)	2.00	liter
6.0	Installation of Ceiling		
	2" x 6m Double Furring	72.00	pcs
	1" x 3m Wall Angle	60.00	pcs
	1.5" x 6m Carrying Channel	69.00	pcs
	Double Wall Clip	506.00	pcs
	3/16thk Hardiflex	103.00	pcs

6.0 Installation of Ceiling		
1/8x 1/2" Blind Rivets	26.00	boxes
1/8" Stainless Drill Bit (for metal)	5.00	pcs
1/8" Stainless Drill Bit (for concrete)	5.00	pcs
Riveter	1.00	pc
Flat Latex	3.00	tin
Semigloss Latex	3.00	tin
Epoxy Primer	5.00	gal
Skim Coat	3.00	bags
2" Gauze Bandage (gasa)	30.00	boxes
Floor Sanding #100 3M	5.00	m
Tinting color (raw sienna)	2.00	liter
Tinting color (yellow)	2.00	liter
7.0 Rewiring of Electrical and installation of Lighting Fixtures		
Wires	1.00	roll
Utility Box	10.00	pcs
2-gang switch	5.00	pcs
2-gang universal outlet	5.00	pcs
Flexible hose	10.00	m
LED Panel Light 12" 24W	7.00	pcs
LED Panel Light 8" 12W	20.00	pcs
11.0 Installation of Floor and wall Tiles at the Comfort Room		
60x60 Unglazed Homogenous Tiles	32.00	pcs
60x60 Glazed Homogenous Tiles	87.00	pcs
Tile Adhesive	43.00	bags
Portland Cement	22.00	bags
Tile Grout	10.00	bags
12.0 Repiping of water and sewer line at the Comfort Room		
PPR Pipe	1.00	lot
Teflon	5.00	rolls
Elbow	5.00	pcs
Treaded Elbow	5.00	pcs
Coupling	5.00	pcs
13.0 Installation of Plumbing Fixtures at the Comfort Room		
Water Closet	2.00	set
Shower	2.00	set
Lavatory Basin	1.00	set
Lavatory Faucet	1.00	pc
S/S Bidet Spray	2.00	pcs
S/S Soap Holder	2.00	pcs
S/S Towel Holder	2.00	pcs
S/S Tissue Holder	2.00	pcs
14.0 Construction of Kitchen Counter		
CHB	28.00	pcs
Portland Cement	8.00	bags
Sand (bistay)	12.00	bags
120x60 Syntetic Granite/Homogenous tiles	2.00	pcs
Tile Adhesive	3.00	bags
Tile Grout	1.00	bag
Tile Trim	1.00	pc
S/S Kitchen sink	1.00	pc
S/S Gooseneck Kitchen Faucet	1.00	pc