

Project Title: **Proposed Renovation of Office of CSI Training Room to OAC-Ronquillo**
 Location: 4th Floor of CSC Main Building Civil Service Commission - Central Office
 Floor Area: 165.00 sq.m.

Bill of Materials and Quantities

<i>Description</i>	<i>Quantity</i>	<i>Unit</i>
4.0 Installation of Floor and wall Tiles at the Comfort Room		
20x30cm Ceramic Wall Tiles	44.00	pcs
Tile Adhesive	9.00	bags
Tile Grout	3.00	bags
5.0 Repiping of water and sewer line at the Comfort Room		
PPR Pipe	15.00	pcs.
Teflon	5.00	rolls
Elbow	6.00	pcs
Treaded Elbow	6.00	pcs
Coupling	6.00	pcs
6.0 Installation of Plumbing Fixtures at the Comfort Room		
S/S Shower Set (complete with fittings)	1.00	set
Lavatory Basin (complete with fittings)	2.00	set
Lavatory Faucet	2.00	set
Water Closet (complete with fittings)	2.00	set
Urinal (complete with fittings)	1.00	set
S/S Tissue Holder	2.00	pcs
Stainless Floor Drain	2.00	pcs
Mirror	2.00	pcs
7.0 Installation of Drywall Partition		
50x75mmx3m Metal Studs	25.00	pcs
50x75mmx3m Metal Track	10.00	pcs
1/4 thk Hardiflex	17.00	pcs
1/8x 1" Blind Rivets	1.00	box
1/8x 1/2" Blind Rivets	5.00	boxes
1/8" Stainless Drill Bit (for metal)	3.00	pcs
1/8" Stainless Drill Bit (for concrete)	3.00	pcs
Riveter	1.00	pcs
Flat Latex	3.00	tin
Semigloss Latex	3.00	tin
Skim Coat	2.00	bags
2" Gauze Bandage (gasa)	15.00	boxes
Floor Sanding #100 3M	3.00	m
Tinting color (raw sienna)	1.00	liter
Tinting color (yellow)	1.00	liter
8.0 Installation of Tubular Steel Vertical Slat Partition		
50mmx75mmx 6m, 1.5mm thk. Tubular	12.00	pcs
Welding Rod #362	3.00	box
Rust converter	1.00	gal
Lacquer enamel	4.00	gal
Epoxy Primer	2.00	gal
Polytuff	1.00	gal
Lacquer thinner	2.00	gal
Lacquer Flo	1.00	gal
Paint brush #3	2.00	pcs
Paint brush #1	2.00	pcs
#1Baby roller brush (foam)	3.00	pcs
#7 Baby roller brush (rag)	3.00	pcs

Rags	1.00	kg
Metal disk (thin)	2.00	pcs
3/8" Drill bit (metal)	3.00	pcs
3/8" Drill bit (masonry)	3.00	pcs
10.0 Installation of Ceiling		
2" x 6m Double Furring	18.00	pcs
1" x 3m Wall Angle	18.00	pcs
1.5" x 6m Carrying Channel	20.00	pcs
Double Wall Clip	155.00	pcs
3/16thk Hardiflex	24.00	pcs
1/8x 1" Blind Rivets	1.00	box
1/8x 1/2" Blind Rivets	6.00	boxes
1/8" Stainless Drill Bit (for metal)	3.00	pcs
1/8" Stainless Drill Bit (for concrete)	3.00	pcs
Flat Latex	3.00	tin
Semigloss Latex	3.00	tin
Quick Dry Enamel	4.00	gal
Paint thinner	1.00	gal
Paint brush #3	2.00	pcs
Paint brush #1	2.00	pcs
#1 Baby roller brush (foam)	3.00	pcs
#7 Baby roller brush (rag)	3.00	pcs
Sand paper 3M #100	2.00	m
11.0 Rewiring of Electrical and installation of Lighting Fixtures		
Wires	1.00	roll
Utility Box	5.00	pcs
2-gang switch	3.00	pcs
2-gang universal outlet	3.00	pcs
Flexible hose	10.00	m
12.0 Repiping of ACU		
Aero Tape	1.00	roll
Rubber Insulation	3.00	pcs
Polythelyne	1.00	roll
15.0 Construction of Kitchen Counter		
CHB	14.00	pcs
Portland Cement	3.00	bags
Sand (bistay)	5.00	bags
120x60 Syntetic Granite/Homogenous tiles	1.00	pcs
Tile Adhesive	1.00	bags
Tile Grout	1.00	bags
Tile Trim	2.00	pcs
Stainless Kitchen sink	1.00	set
16.0 Fabrication and Installation of Kitchen base and overhead cabinet		
3/4 thk Marine Plywood	2.00	pcs
1/4 thk Marine Plywood	1.00	pcs
Concealed Hinges	4.00	pairs
Door Handle	4.00	pcs
Wood Glue	1.00	gal
Magnetic Catches	4.00	pcs
Iron Pin	1.00	box
1" Finishing Nail	1.00	kg
2" Common Nail	1.00	kg
1" Liston	3.00	pcs
Flat Enamel	4.00	gal
Quick Dry Enamel	4.00	gal

Paint thinner	1.00	gal
Paint brush #3	2.00	pcs
Paint brush #1	2.00	pcs
#1Baby roller brush (foam)	3.00	pcs
#7 Baby roller brush (rag)	3.00	pcs
Sand paper 3M #100	1.00	m
Tinting color (raw sienna)	1.00	qtr
Tinting color (yellow)	1.00	qtr