

Project Title: **Proposed CSC Façade Signage**
 Location: Civil Service Commission - Central Office

Program of Work


Description

- 1.0 Construction of Walls and Foundation
- 2.0 Refurbishing of existing perimeter wall
- 3.0 Hauling of Debris
- 4.0 Clean-up

Bill of Materials

<i>Description</i>	<i>Quantity</i>	<i>Unit</i>	<i>Unit Price</i>	<i>Total</i>
1.0 Stainless Signage	1.00	lot	82,000.00	82,000.00
2.0 Granite (Main Wall)	20.00	sq.m	3,500.00	70,000.00
3.0 Granite (Accent Wall)	6.00	sq.m	3,400.00	20,400.00
4.0 Tile Adhesive (ABC)	26.00	bags	290.00	7,540.00
5.0 Portland Cement	10.00	bags	280.00	2,800.00
6.0 Sand	2.00	elf	2,700.00	5,400.00
7.0 4" CHB	240.00	pcs	17.00	4,080.00
8.0 10mm dia. RSB (10")	35.00	pcs.	210.00	7,350.00
9.0 Painting Works	1.00	lot	5,500.00	5,500.00
10.0 Electrical Works	1.00	lot	55,000.00	55,000.00
11.0 Labor for 35 days				140,000.00
		Total	-----	400,070.00
		say	-----	401,000.00
			<i>plus 12% tax</i>	449,120.00

Prepared by:


HOPE T. MAGAUAY
 Architect II -BGMD